B.R.340 · CJP1/2 RECEIVER

PART IV

ARU18A ADAPTOR, COMMON ANTENNA

5820-99-525-6192

### **CONTENTS**

### 1 BRIEF DESCRIPTION AND SPECIFICATION

PLATE 1.1 ARU18A ADAPTOR, COMMON ANTENNA 5820-99-525-6192

- 1.1 BRIEF DESCRIPTION
- 1.2 SPECIFICATION
- 2 INSTALLATION
- **OPERATING INSTRUCTIONS** 
  - 3.1 TUNING ARU18A ADAPTOR, COMMON ANTENNA
  - 3.2 LOCAL RECEIVER BY-PASS
  - 3.3 EMERGENCY AERIAL

### CIRCUIT DESCRIPTION

- 4.1 GENERAL Fig. 4.1 Block Diagram of ARU18A Adaptor, Common Antenna
- 4.2 CIRCUIT DESCRIPTION Fig. 4.2 Simplified Circuit of One Band Filter
- **5 MAINTENANCE**
- REPAIR AND REPLACEMENT
  - 6.1 GENERAL
  - REPAIRS TO TUNED CIRCUIT PCB ASSEMBLY 5820-99-527-1904
  - REMOVAL OF TUNED CIRCUIT PCB ASSEMBLY 5820-99-527-1904

### **FAULTFINDING**

- 7.1 LOW SENSITIVITY
- 7.1.1 Low Sensitivity on All Nine Bands
- 7.1.2 Low Sensitivity on One to Eight Bands
- 7.2 COMPLETE LOSS OF SIGNAL
- 7.2.1 Complete Loss of Signal on All Nine Bands7.2.2 Complete Loss of Signal on One to Eight Bands

#### PERFORMANCE CHECKS AND ADJUSTMENTS

- 8.1 GENERAL
- TEST EQUIPMENT REQUIRED
- 8.3 OVERALL PERFORMANCE CHECKS
- 8.4 ALIGNMENT OF LOW-PASS FILTER
- ALIGNMENT OF BAND FILTERS

### ILLUSTRATIONS AND COMPONENT LIST

- FIG. 9.1 FRONT PANEL CONTROLS
- FIG. 9.2 LAYOUT AND COMPONENT LIST
- FIG. 9.3 CIRCUIT DIAGRAM

1 BRIEF DESCRIPTION AND SPECIFICATION



### 1 BRIEF DESCRIPTION AND SPECIFICATION

### 1.1 BRIEF DESCRIPTION

The ARU18A Adaptor, Common Antenna 5820-99-525-6192 enables the CJP2 Receiver to be operated from a common aerial outfit EAL over the frequency range 1.5 to 30MHz.

#### 1.2 SPECIFICATION

Common Aerial System Line Impedance:  $75\Omega$ 

VSWR at Common Aerial Output Socket SK2: Less than 1.5 at any frequency more than 4% from tune frequency Insertion loss to the Receiver: Less than 7dB at tune frequency

### Frequency Range:

1.5 to 30MHz in nine frequency bands

(a) 1.5 to 2.5MHz

(f) 9.5 to 12MHz

(b) 2.5 to 3.5MHz

(g) 12 to 18MHz

(c) 3.5 to 4.5MHz

(h) 18 to 24MHz

(d) 4.5 to 7.0MHz (e) 7.0 to 9.5MHz (i) 24 to 30MHz

### Controls:

Frequency Range switch Increment tuning

#### Dimensions:

| Height             | Width              | Depth               | Weight |
|--------------------|--------------------|---------------------|--------|
| 3 <del>11</del> in | 7 <del>33</del> in | 16 <del>43</del> in | 51b    |
| 94mm               | 196mm              | 426mm               | 2·27kg |

## 2 INSTALLATION

### 2 INSTALLATION

The addition of an ARU18A Adaptor, Common Antenna unit to a CJP1 receiver; converts the receiver to a type CJP2.

- (1) Unscrew six captive knurled fixing screws on R551N Receiver, Radio.
- (2) Hold R551N Receiver by handles and slide out on runners to limit indicated by an audible click. In this condition the unit cannot be moved either inwards or further outwards.
- (3) Unscrew and remove four 4BA round head chrome fixing screws, together with associated washers and nuts, securing the blank panel at the top left-hand corner of R551N Receiver and remove the panel.
- (4) Fit ARU18A Adaptor, Common Antenna behind panel opening and secure to R551N Receiver front panel with four 4BA round head chrome screws and associated washers.
- (5) Secure unit to R551N Receiver with two 4BA cheese head screws and washers, one screw on each side, at rear of ARU18A Adaptor, Common Antenna.
- (6) Locate two unused coaxial cables, terminated by coaxial plugs, in the cable form near the rear of the ARU18A Adaptor, Common Antenna, labelled PL1 and PL2.

- (7) Fit coaxial lead labelled PL1 to socket SK1, and lead labelled PL2 to socket SK2 on ARU18A Adaptor, Common Antenna.
- (8) Locate miniature coaxial cables clipped to rear panel of R551N Receiver terminated by connectors plug PL5 and socket SK5.
- (9) Disconnect connectors PL5 and SK5.
- (10) Locate free miniature coaxial lead from ARU18A Adaptor, Common Antenna terminated by plug PL1 and connect it to socket SK5 from R551N Receiver, Radio.
- (11) Locate free miniature coaxial lead from ARU18A Adaptor, Common Antenna terminated by socket SK3 and connect it to plug PL5 from R551N Receiver, Radio.
- (12) Press downwards with thumbs on to catch release on each runner and push R551N Receiver inwards about lin.
- (13) Hold R551N Receiver by handles and slide home on runners.
- (14) Secure R551N Receiver to Cabinet, Electrical Equipment 5820-99-525-6193 by the six captive knurled head fixing screws.

972-1

3 OPERATING INSTRUCTIONS

### 3 OPERATING INSTRUCTIONS

# 3.1 TUNING ARU18A ADAPTOR, COMMON ANTENNA

See Fig. 9.1 for Controls.

- (1) Set the R551N Receiver to the required operating frequency.
- (2) Set the ARU18A Adaptor, Common Antenna Frequency Range switch to position appropriate to required operating frequency.
- (3) Note the code letter pertaining to the frequency range set in (2).

| Code<br>Letter | Frequency      |
|----------------|----------------|
| Letter         | Range          |
|                | 1.5 to 2.5MHz  |
| Α              | 2.5 to 3.5MHz  |
|                | 3.5 to 4.5MHz  |
|                | 4.5. 5.03444   |
| _              | 4.5 to 7.0MHz  |
| В              | 7·0 to 9·5MHz  |
|                | 9·5 to 12·0MHz |
|                | 12 to 18MHz    |
| C              | 18 to 24MHz    |
| •              | 24 to 30MHz    |
|                | 47 to JUNITIZ  |

(4) Subtract the lower limit of the Frequency Range selected in (2) from the required operating frequency.

E.g. Required operating frequency: 6.7MHz Lower frequency limit of Frequency Range: 4.5MHz

6.7 - 4.5 = 2.2

- (5) Set the Increment control cursor to number determined in (4) using the scale labelled with the code letter noted in (3). In the example, this letter would be B.
- (6) Finally, adjust Increment control slowly for maximum signal to R551N Receiver, Radio.

#### 3.2 LOCAL RECEIVER BY-PASS

When the Frequency Range switch is set to the LOCAL Rx BY-PASS position the Common Aerial input socket SK1 will be directly connected to the Common Aerial output socket SK2. Thus the local equipment is by-passed and the Common Aerial system connected to the next receiver.

Signal source for the local receiver is then the aerial connected to the R551N Receiver, Radio.

#### 3.3 EMERGENCY AERIAL

To receive via the emergency aerial the Frequency Range switch must be in the LOCAL Rx BY-PASS position and the emergency aerial connected to socket SK3 on Cabinet, Electrical Equipment 5820-99-525-6193.

## 4 CIRCUIT DESCRIPTION

### 4 CIRCUIT DESCRIPTION

#### 4.1 GENERAL

The ARU18A Adaptor, Common Antenna 5820-99-525-6192 enables an associated receiver to be tapped into a low impedance line Common Aerial system carrying signals in the HF spectrum 1.5 to 30MHz.

Fig. 4.1 shows how the unit is used to extract wanted signals from the line whilst providing minimum disturbance to the Common Aerial system and other receivers connected in the same way to it.




Fig. 4.1 Block Diagram of ARU18A Adaptor, Common Antenna

### 4.2 CIRCUIT DESCRIPTION

For circuit diagram, see Fig. 9.3.

The frequency range, 1.5 to 30MHz, is divided into nine bands, each band tunable by a variable filter. As each of these filters is similar, only one of the sections will be described in detail.

Signals from the Common Aerial system at the adaptor line input are fed through the balanced primary winding of RF transformer T1 (see Fig. 4.2) and out to

the next receiver. The inductance of T1 primary, together with capacitors C1 and C2, provide a  $75\Omega$  low-pass  $\pi$ -section filter having a cut-off frequency of about 40MHz.

Signals in the wanted frequency band are inductively coupled to the secondary of T1, which is tuned to the operating frequency by capacitors C3 and C4 in series. The ratio of these capacitors, together with a 30MHz low-pass filter terminated at each end by m-derived half sections, provide impedance matching to the local receiver with high attenuation at the receiver first IF of 38MHz.




Fig. 4.2 Simplified Circuit of One Band Filter

The nine filter bands are divided into three groups of three bands.

| Group A | 1.5 to 2.5MHz<br>2.5 to 3.5MHz<br>3.5 to 4.5MHz |
|---------|---|
| Group B | 4·5 to 7·0MHz<br>7·0 to 9·5MHz<br>9·5 to 12·0MH |
| Group C | 12 to 18MHz<br>18 to 24MHz<br>24 to 30MHz       |

The lowest frequency band filter in each group is the pilot filter, the other two having trimming and tracking capacitors which are adjusted to provide optimum tracking with the Increment scale. On the three highest frequency bands only one section of the ganged tuning capacitor is used, both sections being paralleled for the other six bands.

When the Range switch is set to LOCAL Rx BY-PASS position the local receiver is disconnected from the Common Aerial system, and as sockets SK1 and SK2 are directly connected, the Common Aerial system by-passes the local installation. The local receiver input SK3 is then connected via the 30MHz low-pass filter, to the local receiver aerial filters at plug PL1.

## 5 MAINTENANCE

### 5 MAINTENANCE

- (1) Remove top cover plate secured by eight 4BA fixing screws.
- (2) Remove any dust with vacuum cleaner and Brush 0476-99-943-0408.
- (3) Clean all wafer switch contacts with Switch Cleaning Fluid 044-99-9150-1253.
- (4) Apply a small quantity of silicone grease, e.g. Midlands Silicones type MS4 0474-99-942-4829 to the switch index mechanism.
- (5) The bearings of the mechanisms used for rotating the switch and the variable capacitor should not require attention.
- (6) Refit top cover plate.

6 REPAIR AND REPLACEMENT

### 6 REPAIR AND REPLACEMENT

#### 6.1 GENERAL

After any repairs or replacement of components, the relevant band or bands should be re-aligned as in para. 8.5.

### 6.2 REPAIRS TO TUNED CIRCUIT PCB ASSEMBLY 5820-99-527-1904

Remove four 4BA screws securing the bottom cover plate and lift off the plate. This will allow access to the component soldered connections.

### 6.3 REMOVAL OF TUNED CIRCUIT PCB ASSEMBLY 5820-99-527-1904

(1) Unsolder leads from switch wafers at pins

- I to 36 on the printed circuit board (see Fig. 9.2 for location of pins).
- (2) Unsolder coaxial cable from switch S1dB, inner at pin 37 and screen at pin 38.
- (3) Unsolder coaxial cable from socket SK3, inner at pin 39 and screen at pin 40.
- (4) Remove five 4BA screws securing the printed circuit board and lift the board vertically taking care not to damage the leads still connected to the switch wafers.
- (5) When rewiring the switch leads to the PCB pins, ensure correct connection by reference to Fig. 9.3.

7 FAULTFINDING

### 7 FAULTFINDING

#### 7.1 LOW SENSITIVITY

Determine whether the sensitivity is low on all bands or only certain bands.

#### 7.1.1 Low Sensitivity on All Nine Bands

- (1) If sensitivity is higher at the HF end of all bands than at the LF end, check continuity of wipers on switch wafers S1aB and S1aF (see Fig. 9.3) and wiring to ganged variable capacitor C88, C93.
- (2) Check wiper contacts for continuity on all switch wafers (see Fig. 9.3).
- (3) Check attenuation of low-pass filter L1 to L4, C86, C87 and C91. Re-align, if necessary, as in para. 8.4.

### 7.1.2 Low Sensitivity on One to Eight Bands

(1) If sensitivity is higher at the HF end of faulty bands than at the LF end, check continuity of relevant switch contacts on wafers SlaB and SlaF (see Fig. 9.3).

- (2) Check that switch contacts associated with faulty bands provide continuity or open circuit as required (see Fig. 9.3).
- (3) Check alignment of faulty bands as in para. 8.5.

#### 7.2 COMPLETE LOSS OF SIGNAL

Determine whether the loss occurs on all bands or only certain bands.

### 7.2.1 Complete Loss of Signal on All Nine Bands

- (1) Check coaxial terminations, particularly to plugs and sockets (see Fig. 9.2).
- (2) Check wiper contacts for continuity on all switch wafers (see Fig. 9.3).
- (3) Check wiring to ganged variable capacitor C92, C93.

### 7.2.2 Complete Loss of Signal on One to Eight Bands

- (1) Check that switch contacts associated with faulty bands provide continuity or open circuit as required (see Fig. 9.3).
- (2) Check components associated with faulty bands.

**8 PERFORMANCE CHECKS AND ADJUSTMENTS** 

### 8 PERFORMANCE CHECKS AND ADJUSTMENTS

#### 8.1 GENERAL

This chapter provides information for testing the overall performance of the ARU18A Adaptor, Common Antenna and also for alignment of the band filters.

### 8.2 TEST EQUIPMENT REQUIRED

To complete all the performance checks detailed in this chapter, the following items of test equipment are required:

RF Signal Generator: CRETE CT452A with  $75\Omega$  adaptor

RF Valve Voltmeter: CRETE CT471 with 75Ω Probe 6625-99-195-1983

BNC Coaxial Plug: Greenpar GE35070C10 5935-99-106-8586 with  $75\Omega$  resistive load connected between inner and shell (e.g. two  $150\Omega$  resistors 5905-99-013-5974 in parallel)

### 8.3 OVERALL PERFORMANCE CHECKS

Test Equipment Required (For details see para. 8.2)

RF signal generator

RF valve voltmeter

BNC coaxial plug

- (1) Connect RF signal generator 75Ω output to socket SK1.
- (2) Set RF output level to minimum.
- (3) Connect BNC coaxial plug terminated by  $75\Omega$  to socket SK2.
- (4) Connect flying lead terminated by coaxial socket SK3 to  $75\Omega$  probe on RF valve voltmeter.
- (5) Set RF signal generator output level to 1.0V rms emf and maintain it at this level when changing frequency.
- (6) Set RF signal generator frequency, Range switch and Incremental control as in Table 8.1 below and then adjust the Incremental control for maximum indication on the RF valve voltmeter at each frequency.

Limit: not less than 250mV.

Table 8.1 ARU18A Adaptor, Common Antenna Control Settings for Overall Performance Checks

| RF Signal        |              | Increment         | Control     |
|------------------|--------------|-------------------|-------------|
| Generator        | Range Switch | Approx            | g ,         |
| Frequency<br>MHz | MHz          | Cursor<br>Setting | Scale       |
| 171112           | 141112       | Detting           |             |
| 1.5              | 1.5-2.5      | 0                 | Α           |
| 2.0              | 1.5-2.5      | 0.5               | Α           |
| 2.5              | 1.5–2.5      | 1.0               | Α           |
| 2.5              | 2.5-3.5      | 0                 | Α           |
| 3.0              | 2.5-3.5      | 0.5               | Α           |
| 3.5              | 2.5 - 3.5    | 1.0               | Α           |
| 3.5              | 3.5-4.5      | 0                 | Α           |
| 4.0              | 3.5-4.5      | 0.5               | Ä           |
| 4.5              | 3.5-4.5      | 1.0               | Α           |
| 4.5              | 4.5–7        | 0                 | В           |
| 5.75             | 4.5-7        | 1.25              | B           |
| 7.0              | 4.5-7        | 2.5               | В           |
| 7.0              | 7–9·5        | 0                 | В           |
| 8.25             | 7-9.5        | 1.25              | В           |
| 9.5              | 7–9·5        | 2.5               | В           |
| 9.5              | 9.5–12       | 0                 | В           |
| 10.75            | 9.5–12       | 1.25              | В           |
| 12.0             | 9.5–12       | 2.5               | В           |
| 12.0             | 12–18        | 0                 | С           |
| 15.0             | 12–18        | 3.0               | C<br>C<br>C |
| 18.0             | 12–18        | 6.0               | С           |
| 18.0             | 18-24        | 0                 | С           |
| 21.0             | 18–24        | 3.0               | C           |
| 24.0             | 18–24        | 6.0               | C<br>C      |
| 24.0             | 24–30        | 0                 |             |
| 27.0             | 24–30        | 3.0               | C<br>C      |
| 30.0             | 24–30        | 6.0               | C           |

- (7) Disconnect  $75\Omega$  probe on RF valve voltmeter from coaxial socket SK3.
- (8) Disconnect BNC coaxial plug terminated by 75Ω from socket SK2.
- (9) Connect flying lead terminated by coaxial socket SK3 to BNC coaxial plug terminated by 75Ω.
- (10) Connect  $75\Omega$  probe on RF valve voltmeter to socket SK2.
- (11) Set Range switch to 4.5—7MHz position.
- (12) Set Increment control to 1.0 on scale B, i.e. tune frequency of 5.5MHz.
- (13) Set RF signal generator frequency to 1.5MHz and output level to 1.0V rms emf.

- (14) Observe RF valve voltmeter indication. Limit: not less than 400mV.
- (15) Sweep RF signal generator frequency from 1.5 to 30MHz, maintaining output level at 1.0V rms emf and observing RF valve voltmeter indication. Limit: not less than 400mV except within a bandwidth of ±4% of the tune frequency of 5.5MHz.
- (16) Disconnect test equipment.

### 8.4 ALIGNMENT OF LOW-PASS FILTER

Test Equipment Required (For details see para. 8.2)

RF signal generator

RF valve voltmeter

- (1) Remove eight 4BA screws securing the top cover plate and lift off the plate.
- (2) Connect flying lead terminated by coaxial socket SK3 to RF signal generator  $75\Omega$  output.
- (3) Set RF output level to minimum.
- (4) Connect flying lead terminated by coaxial plug PL1 to  $75\Omega$  probe on RF valve voltmeter.
- (5) Set Range switch to LOCAL Rx BY-PASS position.
- (6) Set RF signal generator frequency to 38·0MHz and output level to 2·0V rms emf.
- (7) Adjust C86 and C91 (see Fig. 9.2 for location) for minimum indication on RF valve voltmeter. Limit: at least 35dB below 1V rms.
- (8) Sweep RF signal generator frequency from 1.5 to 30MHz, maintaining output level at 2.0V rms emf, and observe RF valve voltmeter indication.

  Limit: not lower than 1dB below 1.0V rms.
- (9) Disconnect test equipment.
- (10) Refit top cover plate.

#### 8.5 ALIGNMENT OF BAND FILTERS

Details are given below for alignment of all the nine band filters. When a new Tuned Circuit PCB Assembly 5820-99-527-1904 is fitted, all the filters should be aligned including the low-pass filter (see para. 8.4).

Following repairs to circuitry in specific bands, the alignment instructions relating to those bands only need be carried out.

Test Equipment Required (For details see para. 8.2)

RF signal generator

RF valve voltmeter

BNC coaxial plug

See Fig. 9.2 for location of components.

- (1) Remove eight 4BA screws securing the top cover plate and lift off the plate.
- (2) Rotate the Incremental control to maximum clockwise position, i.e. ganged variable capacitor C92, C93 at minimum capacitance.
- (3) Check that cursor is aligned with horizontal line at the end of the scale.

  If not, loosen the socket head grub screws on the ganged capacitor spindle coupling and adjust cursor position until it is set to horizontal line when capacitor is at minimum capacitance. Then tighten grub screws.
- (4) Set the cores of the relevant RF transformers to the positions indicated in Table 8.2.

Table 8.2 Position of Cores in RF Transformers Before Alignment

| Range<br>Switch<br>MHz | RF<br>Transformer | Position<br>of Core<br>in Former |
|------------------------|-------------------|----------------------------------|
| 1·5-2·5                | T1                | Top                              |
| 2·5-3·5                | T2                | Top                              |
| 3·5-4·5                | T3                | Bottom                           |
| 4·5–7                  | T4                | Bottom                           |
| 7–9·5                  | T5                | Bottom                           |
| 9·5–12                 | T6                | Bottom                           |
| 12–18                  | T7                | Top                              |
| 18–24                  | T8                | Top                              |
| 24–30                  | T9                | Top                              |

- (5) Set trimmer capacitors C16, C26, C33, C44, C55, C73 and C85 to approximately mid-position.
- (6) Connect RF signal generator  $75\Omega$  output to socket SK1.
- (7) Set RF output level to minimum.
- (8) Connect flying lead terminated by coaxial socket SK3 to  $75\Omega$  probe on RF valve voltmeter.
- (9) Connect BNC coaxial plug terminated with 75Ω to socket SK2.
- (10) Set Range switch to 12-18MHz position.
- (11) Adjust Increment control until cursor indicates 0 on scale C.
- (12) Set RF signal generator frequency to 12·0MHz and output level to 1·0V rms emf.
- (13) Using a suitably insulated trimming tool, screw core of T7 inwards until RF valve voltmeter indication is at maximum. Do not continue to screw core inwards as a second, and incorrect, position may be found which also produces a maximum indication on the RF valve voltmeter.
- (14) Set RF signal generator frequency to 18.0MHz.
- (15) Adjust Increment control until cursor indicates 6.0 on scale C.
- (16) Adjust C94 for maximum indication on the RF valve voltmeter.
- (17) Repeat (11) to (16) until no further improvement can be made.
- (18) Check that with the RF signal generator frequency set to 12.5, 13.0, 13.5, 14.0, 15.0, 16.0 and 17.0MHz the cursor indication, when tuned for maximum RF valve voltmeter indication, is within the width of the relevant scale C calibration mark (i.e. 0.5, 1.0, 1.5, 2.0, 3.0, 4.0 and 5.0 respectively).

(19) Repeat (10) to (18) setting Range switch and Increment control to appropriate positions and adjusting relevant components in the sequence shown in Table 8.3.

When adjusting RF transformer cores do not con-

tinue to screw core past the maximum indication on the RF valve voltmeter as a second, incorrect position may be found which also produces a maximum indication.

See Fig. 9.2 for location of components.


Table 8.3 Control Settings, Frequencies and Components Adjusted During Alignment

|          | Range<br>Switch<br>MHz  | Increment<br>Cursor<br>Setting | Control<br>Scale | RF Signal<br>Generator<br>Frequency<br>MHz | RF<br>Transformer | Direction<br>to Screw RF<br>Transformer<br>Core | Capacitor<br>Trimmer |
|----------|-------------------------|--------------------------------|------------------|--|-------------------|---|----------------------|
| 1        | 18-24                   | 0                              | C                | 18.0                                       | Т8                | Inwards   |                      |
| 2        | 18-24                   | 6.0                            | C                | 24.0                                       |                   |   | C73                  |
| 3        | 24-30                   | 0                              | С                | 24.0                                       | Т9                | Inwards   | _                    |
| 4        | 24-30                   | 6.0                            | С                | 30.0                                       |                   |   | C85                  |
| 5        | 1.5-2.5                 | .0                             | Α                | 1.5  | <b>T</b> 1        | Inwards   |                      |
| 6        | 1.5-2.5                 | 1.0                            | Α                | 2.5  |                   |   | C88                  |
| 7        | 2.5-3.5                 | 0                              | Α                | 2.5  | T2                | Inwards   |                      |
| 8        | $2 \cdot 5 - 3 \cdot 5$ | 1.0                            | $\mathbf{A}$     | 3.5  |                   | -   | C16                  |
| 9        | 3.5-4.5                 | 0                              | Α                | 3.5  | T3                | Outwards  |                      |
| 10       | 3.5-4.5                 | 1.0                            | Α                | 4.5  |                   |   | C26                  |
| 11       | 4.5-7                   | 0                              | В                | 4.5  | T4                | Outwards  | <del></del>          |
| 12       | 4.5-7                   | 2.5                            | В                | 7.0  | <del></del> .     |   | C33                  |
| 12<br>13 | 7–9·5                   | 0                              | В                | 7.0  | T5                | Outwards  |                      |
| 14       | 7-9.5                   | 2.5                            | В                | 9.5  | -                 |   | C44                  |
| 15       | 9.5-12                  | 0                              | В                | 9.5  | T6                | Outwards  | <del></del>          |
| 16       | 9.5–12                  | 2.5                            | В                | 12.0                                       |                   |   | C55                  |

(20) Disconnect test equipment.

(21) Refit top cover plate.

ILLUSTRATIONS AND COMPONENT LISTS



### COMPONENT LIST


| CAPA<br>Cl                      | CITORS<br>10pF ±2pF 125V GEC PF/AA  |        | C59<br>C60                                | 390pF ±2% 125V GEC PF/AA 5910-99-913-6618<br>68pF ±2% 125V GEC PF/AA 5910-99-945-1541  |
|---------------------------------|---|--------|---|--|
| C2<br>C3<br>C4<br>C5            | 10pF ±2pF 125V GEC PF/AA<br>100pF ±2% 350V Lemco MS611/I/R/100PG/350<br>1000pF ±2% 125V GEC PF/AB<br>18pF ±1pF 350V Lemco MS611/I/R/18PFP/350   |        | C61<br>C62<br>C63<br>C64                  | 330pF ±2% 125V GEC PF/AA 5910-99-915-0862<br>22pF ±2pF 125V GEC PF/AA 5910-99-945-1534<br>22pF ±2pF 125V GEC PF/AA 5910-99-945-1534<br>82pF ±2pF 125V GEC PF/AA 5910-99-946-2785   |
| C6<br>C7<br>C8<br>C9<br>C10     | 100pF ±2% 125V GEC PF/AA 5910-99-913-6616<br>10pF ±2pF 125V GEC PF/AA<br>10pF ±2pF 125V GEC PF/AA<br>82pF ±2% 350V Lemco MS611/I/R/82PG/350<br>820pF ±2% 125V GEC PF/AB 5910-99-580-7192                                      |        | C65<br>C66<br>C67<br>C68<br>C69<br>C70    | 220pF ±2% 125V GEC PF/AA 5910-99-915-0892<br>27pF ±2pF 125V GEC PF/AA 5910-99-580-7199<br>150pF ±2% 125V GEC PF/AA 5910-99-580-0308<br>270pF ±2% 125V GEC PF/AA 5910-99-913-6605<br>220pF ±2% 125V GEC PF/AA 5910-99-915-0892<br>220pF ±2% 125V GEC PF/AA 5910-99-915-0892 |
| C11<br>C12<br>C13<br>C14<br>C15 | 22pF ±2% 350V Lemco MS611/I/R/22PFP/350<br>100pF ±2% 125V GEC PF/AA 5910-99-913-6616<br>560pF ±2% 125V GEC PF/AB 5910-99-946-9073<br>390pF ±2% 125V GEC PF/AA 5910-99-913-6618<br>39pF ±2% 350V Lemco MS611/I/R/39PFP/350     |        | C71<br>C72<br>C73<br>C74<br>C75           | 180pF ±2% 125V GEC PF/AA 5910-99-945-8379<br>47pF ±2pF 125V GEC PF/AA 5910-99-945-1537<br>4-40pF Mullard 809-08002<br>22pF ±2pF 125V GEC PF/AA 5910-99-945-1534<br>22pF ±2pF 125V GEC PF/AA 5910-99-945-1534   |
| C16<br>C17<br>C18<br>C19<br>C20 | 4-40pF Mullard 809-08002<br>27pF ±2pF 125V GEC PF/AA 5910-99-580-7199<br>27pF ±2pF 125V GEC PF/AA 5910-99-580-7199<br>100pF ±2% 350V Lemco MS611/I/R/100PG/350<br>390pF ±2% 125V GEC PF/AA 5910-99-913-6618                   | ·<br>• | C76<br>C77<br>C78<br>C79<br>C80           | 82pF ±2pF 125V GEC PF/AA 5910-99-946-2785<br>220pF ±2% 125V GEC PF/AA 5910-99-915-0892<br>10pF ±2pF 125V GEC PF/AA<br>56pF ±2pF 125V GEC PF/AA 5910-99-945-1540<br>100pF ±2% 125V GEC PF/AA 5910-99-913-6616   |
| C21<br>C22<br>C23<br>C24<br>C25 | 27pF ±1pF 350V Lemco MS611/I/R/27PFP/350<br>560pF ±2% 125V GEC PF/AB 5910-99-946-9073<br>270pF ±2% 125V GEC PF/AA 5910-99-913-6605<br>270pF ±2% 125V GEC PF/AA 5910-99-913-6605<br>47pF ±2% 350V Lemco MS611/I/R/47PFP/350    |        | C81<br>C82<br>C83<br>C84<br>C85           | 120pF ±2% 125V GEC PF/AA<br>120pF ±2% 125V GEC PF/AA<br>150pF ±2% 125V GEC PF/AA 5910-99-580-0308<br>100pF ±2% 125V GEC PF/AA 5910-99-913-6616<br>4-40pF Mullard 809-08002   |
| C26<br>C27<br>C28<br>C29<br>C30 | 4-40pF Mullard 809-08002<br>33pF ±2pF 125V GEC PF/AA 5910-99-945-1535<br>33pF ±2pF 125V GEC PF/AA 5910-99-945-1535<br>100pF ±2% 350V Lemco MS611/I/R/100PG/350<br>560pF ±2% 125V GEC PF/AB 5910-99-946-9073                   |        | C86<br>C87<br>C88<br>C89<br>C90           | 4-40pF Mullard 809-08002<br>91pF ±2pF 125V GEC PF/AA 5910-99-580-7197<br>3-15pF Part of C92<br>1800pF ±2% 125V GEC PF/AB 5910-99-580-7180<br>2700pF ±2% 125V GEC PF/AB 5910-99-945-7937  |
| C31<br>C32<br>C33<br>C34<br>C35 | 82pF ±2% 350V Lemco MS611/1/R/82PG/350<br>560pF ±2% 125V GEC PF/AB 5910-99-946-9073<br>4-40pF Mullard 809-08002<br>33pF ±2pF 125V GEC PF/AA 5910-99-945-1535<br>33pF ±2pF 125V GEC PF/AA 5910-99-945-1535                     |        | C91<br>C92<br>C93<br>C94                  | 4-40pF Mullard 809-08002<br>8·5-176pF Redifon P44917/3 5910-99-622-9865<br>10-208pF Part of C93  |
| C36<br>C37<br>C38<br>C39<br>C40 | 100pF ±2% 125V GEC PF/AA 5910-99-913-6616<br>470pF ±2% 125V GEC PF/AB 5910-99-945-6555<br>33pF ±2pF 125V GEC PF/AA 5910-99-945-1535<br>180pF ±2% 125V GEC PF/AA 5910-99-945-8379<br>330pF ±2% 125V GEC PF/AA 5910-99-915-0862 |        | INDUC<br>L1<br>L2<br>L3<br>L4             | CTORS Redifon 019/6818A/2 Redifon 019/6818A/2 Redifon 020/6818A/2 Redifon 020/6818A/2  |
| C41<br>C42<br>C43<br>C44<br>C45 | 390pF ±2% 125V GEC 5910-99-913-6618<br>560pF ±2% 125V GEC PF/AB 5910-99-946-9073<br>100pF ±2% 125V GEC PF/AA 5910-99-913-6616<br>4-40pF Mullard 809-08002<br>33pF ±2pF 125V GEC PF/AA 5910-99-945-1535                        |        | RF TR<br>T1<br>T2<br>T3<br>T4<br>T5       | RANSFORMERS  Redifon 010/6818A/2  Redifon 011/6818A/2  Redifon 012/6818A/2  Redifon 013/6818A/2  Redifon 014/6818A/2   |
| C46<br>C47<br>C48<br>C49<br>C50 | 33pF ±2pF 125V GEC PF/AA 5910-99-945-1535<br>100pF ±2% 125V GEC PF/AA 5910-99-913-6616<br>470pF ±2% 125V GEC PF/AB 5910-99-945-6655<br>120pF ±2% 125V GEC PF/AA<br>390pF ±2% 125V GEC PF/AA 5910-99-913-6618                  |        | T6<br>T7<br>T8<br>T9                      | Redifon 015/6818A/2<br>Redifon 016/6818A/2<br>Redifon 017/6818A/2<br>Redifon 018/6818A/2   |
| C51<br>C52<br>C53<br>C54<br>C55 | 220pF ±2% 125V GEC PF/AA 5910-99-915-0892<br>270pF ±2% 125V GEC PF/AA 5910-99-913-6605<br>270pF ±2% 125V GEC PF/AA 5910-99-913-6605<br>68pF ±2% 125V GEC PF/AA 5910-99-945-1541<br>4-40pF Mullard 809-08002                   |        | FERRA<br>FT1<br>SOCK<br>SK1<br>SK2<br>SK3 | ITE BEAD Seimens B62152/A0001X001  ETS Coaxial Greenpar GE37585H 75Ω Coaxial Greenpar GE37585H 75Ω Coaxial Sealectro 51-008-3196   |
| C56<br>C57<br>C58               | 22pF ±2pF 125V GEC PF/AA 5910-99-945-1534<br>22pF ±2pF 125V GEC PF/AA 5910-99-945-1534<br>100pF ±2% 125V GEC PF/AA 5910-99-913-6616   |        | PLUG<br>PL1                               | Coaxial Sealectro 51-007-3196  |


### MPONENT LIST

PLUG PL1


Coaxial Sealectro 51-007-3196

| C59<br>C60                          | 390pF $\pm 2\%$ 125V GEC PF/AA 5910-99-913-6618 68pF $\pm 2\%$ 125V GEC PF/AA 5910-99-945-1541                 |
|-------------------------------------|--|
| C61                                 | 330pF ±2% 125V GEC PF/AA 5910-99-915-0862  |
| C62                                 | 22pF ±2pF 125V GEC PF/AA 5910-99-945-1534  |
| C63                                 | 22pF ±2pF 125V GEC PF/AA 5910-99-945-1534  |
| C64                                 | 82pF ±2pF 125V GEC PF/AA 5910-99-946-2785  |
| C65                                 | 220pF ±2% 125V GEC PF/AA 5910-99-915-0892  |
| C66                                 | 27pF ±2pF 125V GEC PF/AA 5910-99-580-7199  |
| C67                                 | 150pF ±2% 125V GEC PF/AA 5910-99-580-0308  |
| C68                                 | 270pF ±2% 125V GEC PF/AA 5910-99-913-6605  |
| C69                                 | 220pF ±2% 125V GEC PF/AA 5910-99-915-0892  |
| C70                                 | 220pF ±2% 125V GEC PF/AA 5910-99-915-0892  |
| C71                                 | 180pF ±2% 125V GEC PF/AA 5910-99-945-8379  |
| C72                                 | 47pF ±2pF 125V GEC PF/AA 5910-99-945-1537  |
| C73                                 | 4-40pF Mullard 809-08002   |
| C74                                 | 22pF ±2pF 125V GEC PF/AA 5910-99-945-1534  |
| C75                                 | 22pF ±2pF 125V GEC PF/AA 5910-99-945-1534  |
| C76                                 | 82pF ±2pF 125V GEC PF/AA 5910-99-946-2785  |
| C77                                 | 220pF ±2% 125V GEC PF/AA 5910-99-915-0892  |
| C78                                 | 10pF ±2pF 125V GEC PF/AA   |
| C79                                 | 56pF ±2pF 125V GEC PF/AA 5910-99-945-1540  |
| C80                                 | 100pF ±2% 125V GEC PF/AA 5910-99-913-6616  |
| C81                                 | 120pF ±2% 125V GEC PF/AA   |
| C82                                 | 120pF ±2% 125V GEC PF/AA   |
| C83                                 | 150pF ±2% 125V GEC PF/AA 5910-99-580-0308  |
| C84                                 | 100pF ±2% 125V GEC PF/AA 5910-99-913-6616  |
| C85                                 | 4-40pF Mullard 809-08002   |
| C86                                 | 4-40pF Mullard 809-08002   |
| C87                                 | 91pF ±2pF 125V GEC PF/AA 5910-99-580-7197  |
| C88                                 | 3-15pF Part of C92   |
| C89                                 | 1800pF ±2% 125V GEC PF/AB 5910-99-580-7180   |
| C90                                 | 2700pF ±2% 125V GEC PF/AB 5910-99-945-7937   |
| C91                                 | 4-40pF Mullard 809-08002   |
| C92                                 | 8-5-176pF Redifon P44917/3 5910-99-622-9865  |
| C93                                 | 10-208pF Redifon P44917/3 5910-99-622-9865   |
| C94                                 | 3-15pF Part of C93   |
| INDUC<br>L1<br>L2<br>L3<br>L4       | CTORS  Redifon 019/6818A/2  Redifon 019/6818A/2  Redifon 020/6818A/2  Redifon 020/6818A/2                      |
| RF TR<br>T1<br>T2<br>T3<br>T4<br>T5 | ANSFORMERS Redifon 010/6818A/2 Redifon 011/6818A/2 Redifon 012/6818A/2 Redifon 013/6818A/2 Redifon 014/6818A/2 |
| T6                                  | Redifon 015/6818A/2  |
| T7                                  | Redifon 016/6818A/2  |
| T8                                  | Redifon 017/6818A/2  |
| T9                                  | Redifon 018/6818A/2  |
| FERRI<br>FT1                        | TE BEAD Seimens B62152/A0001X001   |
| SOCKI<br>SK1<br>SK2<br>SK3          | ETS Coaxial Greenpar GE37585H 75Ω Coaxial Greenpar GE37585H 75Ω Coaxial Sealectro 51-008-3196                  |






B.R.340 Original





| R    |                        |                |                               |                           |                      |          |          |
|------|------------------------|----------------|-------------------------------|---------------------------|----------------------|----------|----------|
| C,   | 1<br>2<br>7<br>8<br>17 |                | 3<br>4<br>9<br>10<br>19<br>20 | 5<br>11<br>12<br>21<br>22 | 13<br>14<br>23<br>24 | 15<br>25 | 16<br>26 |
| Misc |                        | T1<br>T2<br>T3 |                               |                           |                      |          |          |




DWG No. OO2/6818A/O

972-1







B.R.340 Original

